DEMOLITION NOTES:

1. REMOVE EXISTING HORIZONTAL FAN COIL UNIT AND ALL ASSOCIATED CONTROLS AND WIRING. DISCONNECT ALL EXISTING PIPING AND DUCTWORK. SEE DETAIL 1, SHEET M402 FOR DISCONNECTION POINTS OF PIPING AND DUCTWORK
2. REMOVE EXISTING ROOF MOUNTED EXHAUST FAN AND EXISTING CURB. DISCONNECT ALL ASSOCIATED DUCT, CONTROLS, AND WIRING. SEE DETAIL 2, SHEET M402 FOR DISCONNECTION POINTS OF DUCTWORK AND CURB
3. REMOVE EXISTING BOILER AND DISCONNECT ALL ASSOCIATED PIPING, FLUE DUCTWORK TO THE ROOF PENETRATION, CONTROLS, AND WIRING. SEE DETAIL 1, SHEET M403 FOR DISCONNECTION POINTS OF PIPING
4. REMOVE EXISTING PUMP AND DISCONNECT ALL ASSOCIATED PIPING, WIRING, AND CONTROLS. SEE DETAIL 2, SHEET M401 FOR DISCONNECTION POINTS OF PIPING
5. REMOVE EXISTING AIR COOLED CHILLER AND EQUIPMENT PAD AND DISCONNECT ALL ASSOCIATED PIPING, CONTROLS, AND WIRING. SEE DETAIL 3, SHEET M401 FOR DISCONNECTION POINTS OF PIPING.
6. REMOVE EXISTING GAS FIRED HEATER AND DISCONNECT ALL ASSOCIATED PIPING, CONTROLS, AND WIRING.
7. REMOVE EXISTING CHEMICAL FEED TANK AND DISCONNECT ALL ASSOCIATED PIPING, CONTROLS, AND WIRING.
8. REMOVE EXISTING EXHAUST FAN. EXISTING ROOF CURB AND ROOF TO REMAIN.

CDH
Cleveland Road
Suite 1000
Atlanta, GA 30060-6
770.42
www.cdhpartners.com

COPYRIGHT © 2018 CDH PARTNERS, INC
ALL RIGHTS RESERVED

FULTON COUNTY SCHOOL SYSTEM

RIVER EVES ELEMENTARY SCHOOL - RENOVATION

9000 EVES ROAD
ROSWELL, GA 30076

PROJECT NO: 18046.00

	50% CD'S	06/07/2018
	PERMIT SET	09/20/2018
	95% CD'S	11/08/2018
	BID SET	12/03/2018

GEORGIA REGISTERED PROFESSIONAL ENGINEER DANIEL NOTO

CONTRACT DOCUMENT
ISSUED FOR
CONSTRUCTION

SHEET TITLE
MECHANICAL DUCTWORK PLAN - SECTION A - DEMOLITION

SHEET NUMBER
MD101A

KEY PLAN

GRAPHIC SCALE
8 4 0 8 16
SCALE: 1/8"=1'-0"
UNIT OF MEASURE: FEET

Order Plans @ WWW.LDILine.com