



Order Plans @ www.LDILine.com

**GENERAL NOTES:**

- REFER TO DRAWING ES FOR ROOF PLAN AND ADDITIONAL ELECTRICAL REQUIREMENTS AND EQUIPMENT CONNECTIONS.
- REFER TO DRAWING ES FOR ADDITIONAL ELECTRICAL ROOM INFORMATION.
- COORDINATE CONDUIT REQUIREMENTS AND LOCATIONS WITH THE SITE AND PETROLEUM CONTRACTORS.
- INSTALL CONDUITS AND CONDUITS IN ACCORDANCE WITH NEC REQUIREMENTS FOR VOLTAGE DROP AND DERATING.
- THIS PROJECT HAS A LARGE QUANTITY OF UNDERGROUND CONDUITS. COORDINATE WITH PLUMBING AND STRUCTURAL PLANS TO AVOID UNDERGROUND SPACE CONFLICTS. PROVIDE REQUIRED BURIAL DEPTHS FOR UNDERGROUND CONDUITS TO AVOID SPACE CONFLICTS WITH OTHER DISCIPLINES.
- THE ELECTRICAL CONTRACTOR SHALL EXTEND ALL ELECTRICAL CONDUITS FROM THE STORE TO THE EDGE OF THE CONCRETE CANOPY PAD AND TANK PAD. PETROLEUM CONTRACTOR TO RUN ALL CONDUITS UNDER CANOPY PAD TO CANOPY COLUMNS AND COORDINATE THE HEIGHT OF THE SEAL OFF FITTINGS WITH THE OPENINGS PROVIDED IN THE STEEL COLUMNS. GENERAL CONTRACTOR TO CONNECT AT SEAL OFF FITTINGS IN COLUMNS FOR CONDUIT RUNS FOR LIGHTING AND INTERCOM.

- NOT USED.
- CONDUIT TO BE RUN FROM POINT OF ORIGIN TO ELECTRICAL ROOM OR CLOSEST WALL. REFER TO DRAWING ES FOR ADDITIONAL INFORMATION. REFER TO DRAWING ES FOR ADDITIONAL INFORMATION.
- NOT USED.
- THE ELECTRICAL CONTRACTOR SHALL PROVIDE AND INSTALL ALL CONDUITS. 1-1/2\"/>

- FROM SHOP'S OFFICE:  
1 - 3/4\"/>
- FROM ELECTRICAL ROOM:  
1 - 1/2\"/>
- ALSO PROVIDE (2) 3/4\"/>
- THE ELECTRICAL CONTRACTOR SHALL FURNISH AND INSTALL IN THE MANAGERS OFFICE A DEDICATED SIMPLEX OUTLET TO THE PRICE CHANGING SIGN. ELECTRICAL CONTRACTOR TO INSTALL FILTER PROVIDED BY SIGN CONTRACTOR. THE ELECTRICAL CONTRACTOR SHALL ALSO PROVIDE A 20 AMP WATER PROOF RECEPTACLE POWERED FROM A SEPARATE GENERAL PURPOSE CIRCUIT AT THE BASE OF EACH PRICE CHANGING SIGN.
- THE CANOPY COLUMN CLOSEST TO THE STORE SHALL BE USED FOR INTERCOMS, CAMERA AND MUSIC WHILE THE CANOPY COLUMN FURTHEST FROM THE STORE SHALL BE USED FOR LIGHTING. SITE CONDUITS TO BE COORDINATED WITH SITE SPECIFIC REQUIREMENTS:

- (2) 1\"/>
- STUB UP TO JUNCTION BOX. PROVIDE ELECTRICAL METAL TUBING (EMT) FROM JUNCTION BOX TO RECEPTACLES IN THIS AREA. MOUNT RECEPTACLES ON INSIDE FACE OF COUNTER BACKWALL. RECEPTACLE LOCATION SHALL ALLOW FOR EQUIPMENT TO FIT AGAINST COUNTER BACKWALL.
- STUB UP TO JUNCTION BOX. PROVIDE LIQUID TIGHT FLEXIBLE METAL CONDUIT FROM JUNCTION BOX TO RECEPTACLES FOR CUSTOMER TERMINALS (SEE SHEET E1). MOUNT RECEPTACLES ON OUTSIDE FACE OF COUNTER FRONTWALL.
- ROUGH-IN ELECTRICAL FOR OUTLETS IN THIS PARTIAL HEIGHT BUILDING PRIOR TO DRYWALL INSTALLATION (SEE SHEET E1).
- 1\"/>
- 1\"/>
- 1\"/>
- (3) 1\"/>
- IN ADDITION TO THOSE SHOWN ON SHEET E1, ADD (1) GASOLINE EMERGENCY SWITCH AT THE STREET SIDE OF THE GAS CANOPY POSITION. JUST OFF THE CURB ON THE GRASS. CENTERED ON THE GAS CANOPY MOUNT AT 48\"/>
- PROVIDE 1\"/>
- IF REQUIRED FOR THIS PROJECT PROVIDE THE FOLLOWING: (1) 1\"/>
- FOR RUEL CONDUITS SEE SHEET E3 FOR MORE INFORMATION. CONDUITS IN THIS AREA CAN BE BUNDLED TOGETHER AND DON'T NEED TO BE IN A ROW TO AVOID CONDUIT CONFLICTS. WHEN INSTALLING CABINETS, VERIFY LOCATION OF KNOCKOUTS IN BASE CABINET WITH CABINET VENDOR.



**CLIENT NAME**  
**WAWA**  
 260 WEST BALTIMORE PIKE  
 WAWA, PENNSYLVANIA 19083

**PROJECT NAME**  
**WAWA F110L 2018.01 STORE #5337 - MRC**  
 SE MARICAMP RD & SE 24th ST.  
 OCALA, FL

Revision Schedule	
No.	Description
1	PRELIMINARY SET
2	REV 2018.01
3	PRE-REVISION SET
4	REV SET
5	REV SET