


DEMOLITION KEY NOTES

- ① REMOVE WALLS AND ALL ASSOCIATED ELECTRICAL.
- ② REMOVE DOORS, FRAMES AND ALL ASSOCIATED HARDWARE.
- ③ REMOVE FRONT DOORS AND FRAME. STORE FOR RE-USE.
- ④ REMOVE OVENS.
- ⑤ REMOVE COUNTER, SINK AND ALL ASSOCIATED PLUMBING. MAINTAIN EXISTING PLUMBING STUB OUTS.
- ⑥ REMOVE RAMP AND HANDRAIL.
- ⑦ REMOVE CONCRETE PORCH, STEPS AND CANOPY.
- ⑧ REMOVE CARPET.
- ⑨ REMOVE CASE.
- ⑩ REMOVE PEWS, FRONTS AND KNEELERS. STORE FOR RE-USE. (STORAGE BY OWNERS)
- ⑪ REMOVE WINDOW.
- ⑫ REMOVE STEPS.
- ⑬ REMOVE PORTION OF ALTAR FLOOR FRAMING
- ⑭ REMOVE SEVEN SMALL SHRUBS (BOXWOODS)
- ⑮ REMOVE 20' X 30' CONCRETE SLAB, RAILROAD TIES RETAINING WALL, AND PLYWOOD STAIRS

LEGEND	
	EXISTING WALLS AND DOORS TO BE REMOVED
	EXISTING WALLS AND DOORS TO REMAIN

A
D1 DEMOLITION PLAN
SCALE: 1/4" = 1'-0"



ARCHITECTURE
PLANNING
PROJECT MANAGEMENT

6425 Jordan Road
Daphne, AL 36526
Ph 251-493-0217 Fx 251-493-0218

ADDITIONS TO
ST. JOHN'S CATHOLIC CHURCH
 7488 HERMAN SLEDGE RD. BROMLEY, AL

DATE: 10/4/18
DRAWN: JF
CHECKED: WTP
TITLE: Demolition Plan

REVISION:
NO. DATE:

SHEET:

D1

Order Plans @